

**Director's Review of the Project X
Cost Range Estimate:
Low Level RF**

Brian Chase
Project X Director's Review
March 16, 2009




-
- Scope of Estimated Work
 - Boundary Conditions /Assumptions
 - Basis of Estimate
 - Technical Risks/Associated Cost Exposure
 - Potential Technical Revisions
 - Role of Outside Collaborators
 - Summary



- The primary global function of the RF Control System is to regulate the RF fields in all accelerating cavities to maintain required beam energy and emittance
 - Global regulation requires information from beam based instrumentation and sector vector sums created from multiple stations
 - Exception handling for events such as a quenched cavity
 - Cavity field regulation is performed by the local LLRF system which controls a klystron and two cryomodules
 - Cavity phase regulation is in relation to a Master Oscillator signal via the phase Reference line
- A local LLRF system
 - Receives program requests from global control and localized real-time beam based feedback
 - Demodulates over 60 RF signals from the cryomodules, RF, and beam pickups
 - Provides Cavity Field regulation by control of the klystron drive and the Ferrite Vector Modulators the RF drive fast and slow cavity tuners
 - Provides Cavity Resonance control with motorized and piezo cavity tuners
 - Provides self calibration and diagnostics

Project X RF Station with 2 Cryo-modules





- LLRF interface to other systems
 - Control and Timing system
 - The primary Control System interface is via Ethernet connection to the crate level CPU. This connection scaler settings and reading, alarms and limits and waveform capture
 - LLRF provides synchronous reference clock signals to the Distributed Timing system and receives “LrfStartTrigger” (active high LVDS)
 - HLRF and station interlocks
 - LLRF provides the drive signal to the klystron drive amplifier (10dBm FS)
 - LLRF receives coupled port forward and reflected power signals from Drive amplifier and several waveguide pickups. (10dBm FS @ receiver)
 - LLRF provides a “LrfReady” signal (active high LVDS)
 - Receives an “RfInhibit_n” (active low 50 Ohm)
 - Machine Protection system
 - LLRF provides a “GradientRegulated” signal (undefined interface)
 - LLRF provides a “RfTrip” signal (undefined interface)



- LLRF interface to other systems
 - Cryomodule
 - LLRF receives forward, reflected, and cavity transmitted RF signals for each cavity
 - LLRF drives stepping motors and piezo actuators
 - RF protection system
 - LLRF provides cavity RF signals
 - Instrumentation and Diagnostic
 - LLRF provides RF Phase Reference signals to diagnostic systems
 - LLRF receives beam phase signals from beam detectors

Boundary Conditions & Assumptions



- Anticipated inputs from other efforts
 - Much development work will be done within the current HINS and NML projects. Current activities include A0, HTS, CC2, HINS, NML, ILC
 - We expect to gain from the experience of our collaborators
- Presently not expecting major changes to the Main Injector LLRF system
- Electrician and other trade work is not included
- Drive amplifiers for 325 MHz are in the LLRF budget, not in 1300 MHz





- Main Linac: LLRF equipment will reside in the Klystron Gallery
- Tight regulation of cavity parameters
 - R/Q of cavities - needed for beam based calibration
 - Frequency of passband modes
- Negligible ground motion over the length of the linac
- Internal hardware and software design with outsourced manufacturing
- There will be sufficient RF power headroom for regulation
- LLRF will not be a part of the personnel protection systems
- LLRF will be a secondary system in the machine protection systems
- The ILC construction LLRF Group will have control over most decisions that affect system costs

LLRF Rack Detail



Down-converters
not shown







- Review of existing systems SNS, Jlab, DESY, KEK, FNAL
- Vendor quotes on BOMs with production quantities
 - Receiver - FNAL prototype BOM
 - Controller - FNAL prototype BOM
 - Cable - quote from vendor
 - Piezo controller, vector modulator controller, drive amplifier, phase reference - best estimate
 - Final costs may be lower with a true bidding process
 - See paper documents for details
- Prototypes of major components
- Estimate of uncertainty ~ 30%
 - Copper, steel, management structure and requirements, high reliability requirements, present design level



Cost Summary for Project X - LLRF

	# RF Stations	Cost / Station (k \$)	Total Cost (k \$)
325 MHz Warm Cavities	1	\$ 116.69	\$ 117
325 MHz Cold Cavities	7	\$ 126.02	\$ 882
1300 MHz Beta=0.81	4	\$ 90.02	\$ 360
1300 MHz Beta=1	19	\$ 90.02	\$ 1,710
LLRF Total Station Cost	31		\$ 3,069
Cable plant			\$ 305.51
Master Oscillator			\$ 75.00
Local Oscillator&Dist.			\$ 63.20
Synchronizaton to MI			\$ 80.00
Phase Reference Line			\$ 215.08
Global Energy Controller			\$ 50.00
Machine protection			\$ 155.00
		Total LLRF System Cost (\$k)	\$ 3,858



ID	WBS	Task Name	Duration	Start	Finish	Cost	'09	'10	'11	'12	'13	'14	'15	'16	'17	'18
1	1.3.5	1.3GHz LLRF and Global LLRF Systems	1000 days	Mon 5/6/13	Fri 3/3/17	\$3,013,790.00										
2	1.3.5.1	Beta = 0.81 LLRF Stations	125 days	Mon 4/21/14	Fri 10/10/14	\$360,000.00										
3	1.3.5.2	Beta = 1 LLRF Stations	125 days	Mon 4/21/14	Fri 10/10/14	\$1,710,000.00										
4	1.3.5.3	Cable Plant	125 days	Mon 4/21/14	Fri 10/10/14	\$305,510.00										
5	1.3.5.4	Master Oscillator	125 days	Mon 4/21/14	Fri 10/10/14	\$75,000.00										
6	1.3.5.5	Local Oscillator and Distribution	125 days	Mon 4/21/14	Fri 10/10/14	\$63,200.00										
7	1.3.5.6	Synchronization to MI	125 days	Mon 4/21/14	Fri 10/10/14	\$80,000.00										
8	1.3.5.7	Phase Reference Line	125 days	Mon 4/21/14	Fri 10/10/14	\$215,080.00										
9	1.3.5.8	Global Energy Controller	125 days	Mon 4/21/14	Fri 10/10/14	\$50,000.00										
10	1.3.5.9	Machine Protection	125 days	Mon 4/21/14	Fri 10/10/14	\$155,000.00										
11	1.3.5.10	1.3 GHz LLRF Final Design	250 days	Mon 5/6/13	Fri 4/18/14	\$0.00										
12	1.3.5.11	1.3 GHz LLRF Fab/Assy/Test	250 days	Mon 10/13/14	Fri 9/25/15	\$0.00										
13	1.3.5.12	1.3 GHz LLRF Installation & Checkout	375 days	Mon 9/28/15	Fri 3/3/17	\$0.00										



ID	WBS	Task Name	Duration	Start	Finish	Cost	'09	'10	'11	'12	'13	'14	'15	'16	'17
1	1.2.9	325MHz LLRF	1028 days	Tue 7/3/12	Thu 6/9/16	\$999,000.00									
2	1.2.9.1	325 MHz LLRF Final Design	250 days	Tue 7/3/12	Mon 6/17/13	\$0.00									
3	1.2.9.2	325 MHz Warm Cavities	125 days	Tue 7/2/13	Mon 12/23/13	\$117,000.00									
4	1.2.9.3	325 MHz Cold Cavities	125 days	Tue 7/2/13	Mon 12/23/13	\$882,000.00									
5	1.2.9.4	325 MHz LLRF Fab/Assy/Test	250 days	Fri 1/3/14	Thu 12/18/14	\$0.00									
6	1.2.9.5	325 MHz LLRF Installation & Checkout	375 days	Fri 1/2/15	Thu 6/9/16	\$0.00									



- Field regulation of multiple cavities from a single RF power amplifier using Ferrite Vector Modulators
 - Requires precise field control of each cavity's amplitude and phase
 - 325 MHz coaxial modulators & 1300 MHz waveguide modulators
 - Power handling
 - Control Bandwidth
- Resonance control of spoke resonator cavities
- Regulation with low Klystron power overhead
 - Nonlinear klystron behavior including AM to PM coupling
- Viability of low cost phase reference line and long run fiber
- The RD&D plan addresses all of these risks
 - For LLRF concerns, only FVMs are a large cost risk to the project
 - Simulations look promising

Potential Technical Revisions



- State of the art RF electronics changes rapidly and will affect circuit and possibly system topology. A ten years extrapolation into the future is a stretch but the sign of most cost change is generally in our favor
 - Crate standards including possibly no crate
 - Direct sampling of RF signals
 - Radiation hardness of components – sample at the cryomodule
 - Technology for fiber and copper reference distribution
 - Next generation FPGAs and ADCs
 - New technologies
 - No big cost drivers
- LLRF role in MPS is presently largely undefined
 - Design decisions could add complexity and expense



-
- We are currently working with Alessandro Ratti and Larry Doolittle from LBNL. This will develop with a completed MOU
 - Ongoing collaboration with ILC groups from KEK and DESY
 - Ongoing collaboration with Argonne
 - Close ties with JLAB
 - Internal collaboration at Fermilab from AD, CD, and TD



- The basic generation of LLRF hardware and software is becoming well understood. We can build it and make it work
- LLRF is a low cost and fairly low risk system on its own
 - It can be made into an effective controller
- Project X has several innovative technologies that may challenge regulation
 - Driving many cavities from one klystron by using Ferrite Vector Modulators
 - SRF Spoke Resonators in pulsed RF configuration
- RD&D at HINS and NML are critical to Project X LLRF development



-
- Thank You!





- ESECON controller
 - Hardware
 - We have 10 working boards.
 - 3 at A0 photoinjector
 - 1 for HTS at Meson lab.
 - 1 for CCII at NML.
 - Firmware
 - All basic modules are working.
 - The firmware work will continue adding new blocks such as klystron linearization, beam loading compensation, a more sophisticated control, automation and calibration, etc
 - Software
 - We will support DOOCS operation and some level of development. It would be nice to migrate ESECON to the main Controls software for Project X.
 - Commissioning, operations and studies
 - Will be supported.




-
- Real Time Simulator (RTS)
 - The RTS currently supports 4 cavities.
 - The current simulator models include superconducting and normal conducting cavities, individual cavity synchronous phases and beam loading conditions.
 - Future work:
 - Expand the RTS to simulate a full Project X RF unit and Project X front end LINAC.
 - Improve the user interface.
 - Off line simulations
 - CD will complement AD effort in off line simulations for Project X.
 - CD will team up together with AD/LLRF to develop common models for the existing Matlab off line LLRF simulator.



-
- LLRF models
 - Complement AD/LLRF effort in modeling the LLRF problem for Project X.
 - Develop a machine parameter configuration to optimize RF fields in the cavities.
 - Calibration procedures.
 - Analyze and incorporate RF disturbances into the models.
 - Collaborate with TD in their Lorentz force detuning modeling.
 - LLRF Control
 - Advance in the development of control algorithms.
 - Incorporate new control algorithms in the off line and real time simulations.
 - Implement the algorithms in firmware and measure results on field.
 - Support Project X management
 - Support costing and documentation for reviews.
 - Participate of meetings and workshops.
 - Publish results.



Steady state power during beam loading



Power variations during a pulse