

Jlab's 12GeV Cryogenic System Design Experience to Date

Dana M. Arenius

Engineering Division, Cryogenics Dept Head
12GeV Project, Cryogenics Control Manager
Co-Director JLab Cryogenic Collins R&D Institute

FNAL Project X Review
Sept 11-12 2009


Outline

- 12GeV Cryogenics Upgrade Overview
- Project Documentation
- Fundamental Decisions
- Cost Estimate
- Schedule
- Status
- * Summary

Cryogenic System Overview


Cryogenics System Overview

Install Hall D Refrigerator,
200W @ 4.5K



Procure & Install
2nd CHL Refrigerator
4600W @ 2K plus 12kW @
35K plus 25 g/s liquefaction

Cryogenic Overview-CHL#2 Major Equipment




NASA/JLab Collaboration Helium Compressors

Build to Print

3x effective oil removal,
smaller vessels

Electric down from 5.5 to 4 MW
lower capital cost, smaller #



CHL 4.5K 4.6 kW Cold Box Indoor and Outdoor Sections

40% less LN2 use

No Pit, No Roof Hatch

Fits into existing building

Cryogenic Introduction-Other CHL Components

Gas Management Rack



LHe Storage Dewar



4160V Motor Controllers




Oil Removal Vessels



Gas Storage Vessels (1)



CHL Equipment Layout



CHL Compressor Building




Building Steel Being Erected
Aug 2009

Compressor Electrical
Conduits in Floor Slab
July 2009




CHL Installation Piping Design



Warm Helium Compressor
Piping

Hall D Major Refrigeration Equipment

JLab Model 2800
Refrigerator




JLab Helium Compressor



Documentation

Project Documentation



Documentation Sequence

Process Cycle Study (CD-0)
Engineering/Safety Standards
System Block Diagram
Rough Budgetary Estimate
Civil Requirements
Subsystem P&IDs (CD-1)
Equipment Lists
Integrated System Safety Review
Preliminary PED Review
Detailed PED Documentation
Refined Estimates/EIR Review (CD-1/2)
Final PED/Safety Review, CD-2
Construction Phase, CD-3

FUNDAMENTAL DECISIONS

Fundamental Decisions

- **WHAT PROCESS CYCLE ? COUPLE OF CHOICES.....**
 1. **STANDARD CYCLE DESIGN...** Based on single or multiple fixed operating process conditions.....usually fixed T-S diagram for operational control parameters for loads anticipated or estimated
 - VERY UNLIKELY TO BE THE ACTUAL BEST PROCESS CYCLE
 - Normal component performance tolerance variations shift the process conditions at which the refrigerator should be operated
 - Actual refrigerated loads end up not as estimated 
 - Loads have the tendency of changing with time
 - Old saying...no two machines are alike

Have to establish new operating parameters/controls after refrigerator components were designed and built for different conditions, May have limited flexibility

Fundamental Decisions

- **WHAT PROCESS CYCLE? COUPLE OF CHOICES...(cont)**
 2. Process cycle which provides constant high efficiency and stability over a full domain of continuous possible operating points where the operating conditions are automatically determined by the system as the load varies.
 - Demonstrated at the Johnson Space Center (JSC) via Jlab/NASA collaboration
 - JSC has new 20K refrigeration system on order to this cycle concept, which industry has confirmed these characteristics
 - Operating modes were outlined within specifications which defined the boundary of the operating domain region.

JLab adopted choice #2 for 12GeV

Fundamental Decisions

- **WHO DOES THE INTEGRATED SYSTEM DESIGN?**
 - Choices increase in-house or vendor “turn key”
 - JLab has large number of existing infrastructure to which the new system was to be integrated
 - Transfer line, helium storage, gas purification, controls, building space, etc.
 - The existing infrastructure is to continue to support experimental operations for most of the project

JLab decided to perform the integration design in lieu of vendor “turn key”

Cost Estimate

Early Input to Other Departments


- **Example...Civil (ICD)**
 - Space requirements
 - Equipment Layout
 - Electric and Cooling Water
 - Floor Loading
 - Equipment Installation Plan
 - Ventilation and Heating
 - Crane Requirements
 - Lighting
 - Pipe Trench/Slab Conduits

Cryogenics Cost Methodology

Basis of Estimate (BOE):

- Costed 0%
- Obligated 0%
- Quotes from vendors 0%
- Catalog price 0%
- Estimates from vendors/
consultants 74%
- Previous JLab experience 26%
- Information from other labs,
Universities, etc. 0%
- Engineering judgment 0%

Cost Estimate Flow Diagram



CD-0 through CD-2

Cost Estimate Experience

- **Cost instabilities**

- Metals Market.....Stainless and Carbon Steel (2x)
- Foreign Exchange Rates (1.4x)
- Oil Prices (1.1x)
 - Share same fabrication facility as gas and oil industry
 - Cryogenic fabrication must compete with shop profit margins of gas and oil equipment when fuel prices rise and the demand for refining equipment rises
- ARRA impact...unknown as yet

Scheduling Experience

- **SEQUENCE...**
 - **Process Cycle Determination**
 - **Process cycle sets the requirements of the cold box design.. Cold box delivery is ~24 months, cold box heat exchangers and turbines must be ordered with a few months of cold box award, heat exchanger designs must be checked carefully before they are ordered, first 12 months is generally engineering duration followed by fabrication. Preliminary and final engineering design reviews necessary before fabrication is authorized**

Scheduling (cont)

- **Cold Box design sets requirements of warm helium compressor design....compressor delivery is 18 months, ordered no later than 4-6 months after cold box...generally like 2-3 months of test time slot before testing cold box which allows fault correction time**
- **Civil construction runs in parallel (or before) compressor order. Utilities (electric/water) and building construction BOD must be ready for compressor testing. One may not have the full equipment vendor engineering details complete at the time needed for the civil design activity**
- **Gas management, controls, oil removal, etc. run in parallel with compressor ordering time.**

STATUS

Status Overview

- 95% Overall Engineering/Design Complete
- 65% Complete Installation Design Package
 - Final Vendor Input Needed
- 73% of equipment and materials released for procurement

Experience Summary

Topics Discussed

- 12GeV Cryogenics Upgrade Overview
- Project Documentation
- Fundamental Decisions
- Cost Estimate
- Schedule
- Status