

High Intensity Neutrino Source Report
for
DOE Site Visit on B&R Code KA15-02-011

Bob Webber
August 23, 2010

Project X FY10 – HINS Accomplishments




- Began construction of HINS beam line radiation shielding enclosure
- Installed and commissioned the HINS RFQ once again following RF seal repair at the vendor's facility
- Achieved 2.5 MeV beam from RFQ; then removed RFQ to repair water-to-vacuum leaks
- Completed installation of cryogenics delivery system and cavity test cryostat for HINS 325 MHz cavity test facility
- Assembled first 325 MHz SSR1 cavity into helium jacket
- Successfully completed full-field test of first jacketed 325 MHz SSR1 cavity to 27 MV/m @4K
- Received delivery of the full complement of copper RT-CH cavities from industrial vendor
- Completed assembly of first superconducting solenoid magnet into its cryostat and completed initial magnetic testing of the assembly

Project X
Project X


Began Construction of Beam Line Shielding Enclosure



Repaired RFQ --- Re-installed and Re-commissioned



First 2.5 MeV Beam through HINS RFQ on January 13, 2010




Signals from toroid and two BPM buttons, all downstream of the RFQ

Upper display: 2 μ sec/div

Lower display: 20 nsec/div

Lower display shows 44nsec transit delay expected for 2.5 MeV beam between the BPM two buttons separated by 0.96 meters

Beam current is about 3 mA



Profile measurements of 2.5 MeV beam from HINS RFQ

Project X
Project X


325 MHz Cavity Test Facility --- Cryogenics Delivery System and Cryostat Installed




Assembled First SSR1 Cavity with Helium Jacket and Tuner



Project X **First SSR1 Jacketed Cavity Installed in Cavity Test Cryostat**





SSR1-01 Performance in HINS Cavity Test Facility



Accepted Final Delivery of Sixteen HINS RT-CH Cavities



First HINS Solenoid Magnet Cryostat Assembly & Tests



Additional FY10 HINS Accomplishments



- Produced near-final Safety Assessment and Radiation Shielding Assessment documents for the HINS beam facility
- Placed purchase order for spare 325 MHz RF klystron - \$560,000
- Placed purchase order for ten 325 MHz SSR1 cavities from Roark/NioWave - \$360,000
- Began serious assessment of how past HINS development work on pulsed linac systems is best leveraged to the advantage of a CW Project X linac
 - Studied 325 MHz Single Spoke cavity and helium vessel design modifications for CW operation at 2°K
 - Initiated design modifications required for sub-atmospheric, 2°K, operation of the 325 MHz cavity test facility
 - Worked to identify critical beam tests that might be supported



- HINS Linac beam facility
 - Will be absorbed into and managed with pre-Project X activities
 - Funding for this will be moved from KA15-02-011 to the Future Accelerators R&D B&R account
- HINS 325 MHz superconducting RF spoke cavity development
 - Will be absorbed into and managed in an integrated manner with the overall Fermilab superconducting RF cavity development effort
 - Will continue to be funded by KA15-02-011
- KA15-02-011 also funds 650 MHz elliptical cavity development



FY11 HINS Beam Facility Scope of Work – Future Accelerators R&D B&R



- Complete construction of HINS beam line radiation shielding enclosure in MDB
- Obtain final operational approvals for the HINS Linac
 - Submit and review the Radiation Shielding Assessment
 - Submit and review the Safety Assessment Document
- Re-establish 2.5 MeV beam from RFQ
- Quantify parameters of 2.5 MeV beam from RFQ
- Replace existing HINS proton ion source with an H^- ion source
- Configure the HINS beam line for the “Six-Cavity Test” to verify high power RF vector modulator performance with beam in preparation for Project X beam chopper tests
- Begin pursuit of the Project X beam chopper test
 - Finalize beam line design
 - Specify needed components
 - Begin initial component procurement as budget permits



325 and 650 MHz Programs - B&R Code KA15-02-011



- In FY11 and beyond, SRF technology efforts across all frequencies will be integrated
 - Common planning, budgeting and staffing
 - Collective prioritization of activities
 - Shared design/analysis tools, engineering procedures, lessons learned...
- 650 MHz and, to a lesser extent, 325 MHz will build on successful 1.3 GHz SRF accomplishments
 - Use existing SRF infrastructure with modifications where required
 - Continue collaborations with other labs (national and international) that have been established as part of the ILC/SRF Programs
 - Utilize the same skilled workforce and established procedures
- 325 Spoke cavities require further development and cry for first beam test
- Elliptical cavities near 650 MHz are used for other programs
 - 704 MHz (CERN), 805 MHz (SNS)
 - Nevertheless, the 650 MHz is a new cavity frequency that must be developed in detail

FY11 - 325 MHz Cavity Program Scope of Work



- Reconfigure SSR1-0 (now in the 325 MHz Cavity Test Facility with high Q_{ext} drive antenna) with a beam line power coupler and perform full high power pulsed testing
- Jacket second SSR1 and test in HINS 325 MHz Cavity Test Facility
- Finalize integrated design of 2°K, CW SSR cavity and tuner system
- Complete construction of:
 - Two SSR1 cavities now being built at IUAC (India)
 - Ten SSR1 cavities now being fabricated at Roark/NioWave
- Design and install modifications to the 325 MHz cavity test facility cryostat and cryogenics delivery systems to support sub-atmospheric, 2°K and CW operation
- Complete RF and mechanical design of Project X SSR0 cavity and possibly begin fabrication of the first article



FY11 - 325 MHz Cryomodule Program Scope of Work



- Design a short (~four cavity) prototype Project X spoke cavity cryomodule
 - Integrate SSR cavities, tuners, power couplers, solenoid magnets and beam instrumentation components
 - Ultimately destined for beam test in HINS Linac
- Continue prototype work on solenoid magnets for SSR cryomodule
- Finish assembly of three HINS individually-cryostated solenoid magnets
 - Complete magnetic testing
 - Investigate warm-to-cold alignment issues

Project X FY11 - 650 MHz Scope of Work



- Modify existing EP facility and VTS for 650 MHz cavities
- Fabricate required handling and assembly fixtures
- Process & test single-cell 650 MHz $\beta = 0.9$ cavities (ANL, FNAL, India)
 - Six single-cell $\beta = 0.9$ cavities are being ordered in FY10
- Extend the RF and mechanical design of 650 MHz cavities to five-cell structures
- Continue support for work at collaborating institutions
 - JLab: Single-cell $\beta = 0.6$ design, prototype, process & test, CM study
 - ANL: Process $\beta = 0.9$ cavities, design study (elliptical vs. TSR)
 - India: single-cell $\beta = 0.9$ design and prototype, modified Type 4 CM design
- Depending on financial status and technical progress, order first prototype of 5-cell 650 MHz cavity
- Design radiation shielding enclosure for 650 MHz cavity test facility in MDB
- Specify and procure cryogenic delivery system components for 650 MHz cavity test facility in MDB




- FY10
 - A year of major accomplishments for the HINS program
 - A year of planning and preparing for upcoming organizational and programmatic transitions
- FY11 will see management and organization of the historic HINS program completely integrated into the SRF and Project X programs
- FY11 will see program goals re-defined in direct support Project X and SRF objectives
- A large scope of work is identified for FY11
 - Within the B&R Code KA15-02-011 for 325 MHz and 650 MHz superconducting cavity and cryomodule development activities
 - Within Future Accelerator R&D B&R Code for HINS Linac support of Project X objectives





Design based on 3 families of 325 MHz Single Spoke resonators, two families of 650 MHz elliptical cavities, then 1300 MHz ILC cavities

Ion source, RFQ



Summary of 3 GeV CW linac cavities

Section	Energy range MeV	β	Number of cavities	Type of cavities	Maximal power per cavity*, kW
SSR0 ($\beta_G=0.12$)	2.5-10	0.073-0.146	26	Single spoke cavity.	0.5
SSR1 ($\beta_G=0.22$)	10-32	0.146-0.261	18	Single spoke cavity.	1.5
SSR2 ($\beta_G=0.4$)	32-160	0.261-0.52	44	Single spoke cavity.	3.2
650 MHz ($\beta_G=0.61$)	160 - 500	0.52-0.758	42	Elliptic cavity	11.5
650 MHz ($\beta_G=0.9$)	50 - 2000	0.758-0.95	96	Elliptic cavity	18.5
1300 MHz ($\beta_G=1$)	2000-3000	0.95- 0.97	64	Elliptic cavity	16




***Without overhead**

Summary of Cavity Parameters for PX



cavity type	Freq. MHz	L_{eff} mm	E_{acc} MV/m	E_{max} MV/m	B_{max} [mT]	R/Q Ω	G Ω	$Q_{0,2K}$ $\times 10^9$	P_{2K} [W]
LB650, 5-cell, $\beta=0.61$	650	705	16.6	37.5	70	378	191	15	24.1
HB650, 5-cell, $\beta=0.9$	650	1038	18.6	37.3	70	638	255	20	29.2
ILC, 9-cell, $\beta=1$	1300	1038	16.9	34	72	1036	270	15.0	19.8

SSRO cavity design



- Few iterations in concepts of cavity / solenoid designs to minimize period (**690 → 605 mm**)
- In lattice was used: **$L_p = 610$ mm**
- Solenoid with BPM and correctors is to be designed
- Mechanical design: minimizing of df/dP
- RF coupler design is in progress
- Tuners design

F(MHz)	325	MHz
β_{optimal}	0.117	
R_{cavity}	204.3	mm
$L_{\text{wall-to-wall}}$	175.5	mm
R/Q	110	Ω
G	52	Ω
$E_{\text{max}}/E_{\text{acc}}$	5.97	
$H_{\text{max}}/E_{\text{acc}}$	6.89	mT/(MV/m)
$D_{\text{eff}} = (2\beta_{\text{opt}} \lambda / 2)$	108	mm

SSR1 cavity:



Section period

750 mm → 800 mm

(increased after review)

Cavity status

- 2 prototypes tested (Max gradient 34MV/m at 2K)
- 1st SSR1 dressed
- +2 in production in India
- +10 order from Roark

Solenoid status


- Design is completed 2008
- Prototype in production

Cryomodule

- Design of spoke resonator cryomodule is starting

Problems

- Initially the cavity was optimized for pulse operation. For CW operation modifications may be required.



F(MHz)	325	MHz
β_{optimal}	0.21	
R_{cavity}	245.7	mm
$L_{\text{wall-to-wall}}$	295	mm
R/Q	242	Ω
G	84	Ω
$E_{\text{max}}/E_{\text{acc}}$	3.93	
$H_{\text{max}}/E_{\text{acc}}$	5.8	mT/(MV/m)
$D_{\text{eff}} = (28 \lambda / 2)$	193	mm


DOE Site Visit - B&R/A-15-2011
Bob Webber

SSR2 section: cavity, solenoid

SSR2 cavity


- RF design - done (possible changes)
- Mech. design is to be completed.

Latest changes not reflected



Solenoid:

- Design completed
- Prototype ready for test (w/o vessel)




Operating frequency	325	MHz
β_G	0.4	
Cavity Length <small>from wall to wall</small>	406	mm
Dressed cavity length	~530	mm
Cavity diameter	556.2	mm
R/Q	322	Ω
G-factor	112	Ω
Max. gain per cavity ($\phi=0$)	3.16	MeV
Max. surface electric field	33	MV/m
Max. surface magnetic field	54	mT

Bore diameter	30	mm
Available slot length	<294	mm
Squared magnetic field integral	580	T ² -cm
Integrated strength of steering dipoles*	0.5	T-cm
Operating current	< 200	A
Fringe field on the walls of cavities	<10	μ T


* Corrector provides ~6 mm solenoid centre correction

Period (sol+cav+cav+60 mm) = 1300 mm

Dr. Eric Voss, BNL, KA102-01
Bob Webber




650 MHz, 5-cell cavities



β_G	0.61	0.9	
Length (from iris to iris)	705	1038	mm
Aperture	83	100	mm
Cavity diameter	389.9	400.6	mm
R/Q, Ohm	378	638	Ω
G - factor	191	255	Ω
Max. gain per cavity ($\phi=0$)	12.0	19.9	MeV
Gradient	17.1	19.2	MV/m
Max surface electric field	38.6	38.4	MV/m
Max surf electric field	72	72	mT




Preliminary layout of a $\beta=0.9$ 650 MHz 5-cell cavity



- EM design of the cavity is finished;
- Mechanical design is underway: df/dP , tuners, RF coupler
- HOM couplers?

650MHz coupler, preliminary mechanical design

- One window;
- Non- adjustable
- Air-cooled;
- No HV bias.



Max. E-field in air is **4.3 kV/cm**
for **30 kW** input power

Pulse power limitation \approx **650 kW (TW)**

	2K (Flow/Plant),W	5K(Flow/Plant), W	70K(Flow/Plant), W	Total plant,W
RF = 0kW	0.04 / 28.1	0.99 / 196	7.85 / 62.8	287
RF = 20kW	0.065 / 45.7	1.27 / 251.5	8.55 / 68.4	366
RF = 30kW	0.078 / 54.8	1.41 / 279.2	8.87 / 71.0	405

Summary of the Cavity Parameters


Low energy SC Linac (2.5 - 160 MeV)

cavity type	F req MHz	U _{acc, max} MeV	E _{max} MV/m	B _{max} mT	R/Q, Ω	G, Ω	Q _{0,2K} ×10 ⁹	P _{max,2K} W
SSR0, β=0.117	325	0.78	53	59.5	120	57	9.5	0.77
SSR1, β=0.22	325	1.53	34.4	50.8	242	84	14.0	0.94
SSR2, β=0.4	325	3.16	33	54	322	112	18.0	2.07

High energy SC Linac (160 - 3000 MeV)

cavity type	Freq. MHz	L _{eff} mm	E _{acc} MV/m	E _{max} MV/m	B _{max} [mT]	R/Q Ω	G Ω	Q _{0,2K} ×10 ⁹	P _{2K} [W]
LB650, 5-cell, β=0.61	650	705	17.1	38.6	72	378	191	15.0	24.1
HB650, 5-cell, β=0.9	650	1038	19.2	38.4	72	638	255	20.0	29.2
ILC, 9-cell, β=1	1300	1038	16.9	34	72	1036	270	15.0	19.0


Project X RFQ and 2.5 MeV Beamline



Project X RFQ and 2.5 MeV Beamline





Spoke Cavity Input Coupler Test Stand



First full-power coupler tests have been successfully completed

Wall Thickness for 650 MHz



Max. sag of an ILC cavity is 123 μm for 2.8mm wall thickness.

We selected the wall thickness ~ 4 mm.

650 MHz, beta=0.9, 5 –cell cavity geometry


Project X




Left cell

Regular cell


Right cell



r	50
R	200.277
L	106.971
A	82.5
B	84.5
a	20
b	39.5
α	7.02



r	50
R	200.277
L	103.75
A	82.5
B	84
a	18
b	38
α	5.2°



r	50
R	200.277
L	106.971
A	82.5
B	84.5
a	20
b	39.5
α	7.02

DOE Site Visit - B&R KA15-02-011 - Bob Weber

All dimensions are in mm.