

Project X: A New Multi-MW Proton Source at Fermilab



Sergei Nagaitsev
On behalf of many colleagues
PAC 2011
April 1, 2011




Fermilab Long Range Plan

Fermilab is the sole remaining U.S. laboratory providing facilities in support of accelerator-based Elementary Particle Physics. Fermilab is fully aligned with the strategy for U.S. EPP developed by HEPAP/P5.

⇒ ***The Fermilab strategy is to mount a world-leading program at the intensity frontier, while using this program as a bridge to an energy frontier facility beyond LHC in the longer term.***

Project X is the key element of this strategy.






Metrics to Measure Proton Accelerator Capabilities for Intensity Frontier

1. Average beam power on target
 - By far, the most important metric
2. Beam energy on target
 - Muons: ~ 0.8 GeV – 15 GeV
 - Kaons: ≥ 3 GeV
 - Neutrinos: \geq few GeV
 - Nuclear: 1-2 GeV
3. Bunch format (or bunch timing)
 - Small duty-factor for neutrinos (minimize background)
 - Special formats for NF/MC
 - CW for all others
 - Bunch spacing depends on decay time

This science has attracted competition: The proton source landscape this decade...




From Proton Driver to Project X



-
- Fermilab has recognized the need for a new proton source more than 10 year ago.
 - Has been part of Fermilab strategy
 - Present missions are largely based on a HEPAP/P5 report (May, 2008)
 - Configurations varied from a synchrotron to an SCRF linac.
 - Present (reference design) configuration has been “frozen” since mid. 2010.


Project X Mission Goals

- A neutrino beam for long baseline neutrino oscillation experiments
 - 2 MW proton source at 60-120 GeV
- High intensity, low energy protons for kaon and muon based precision experiments
 - Operations simultaneous with the neutrino program
- A path toward a muon source for possible future Neutrino Factory and/or a Muon Collider
 - Requires ~4 MW at ~5-15 GeV .
- Possible missions beyond HEP
 - Standard Model Tests with nuclei and energy applications





Reference Design






Reference Design Capabilities

- 3 GeV CW superconducting H- linac with 1 mA average beam current.
 - Flexible provision for variable beam structures to multiple users
 - CW at time scales $>1 \mu\text{sec}$, 15% DF at $<1 \mu\text{sec}$
 - Supports rare processes programs at 3 GeV
 - Provision for 1 GeV extraction for nuclear energy program
 - 3-8 GeV pulsed linac capable of delivering 300 kW at 8 GeV
 - Supports the neutrino program
 - Establishes a path toward a muon based facility
 - Upgrades to the Recycler and Main Injector to provide ≥ 2 MW to the neutrino production target at 60-120 GeV.
 - Day one experiment to be incorporated utilizing the CW linac
- ⇒ Utilization of a CW linac creates a facility that is unique in the world, with performance that cannot be matched in a synchrotron-based facility.



Project X vs. other facilities



CW linac and RF splitter

- Very powerful combination to support several experiments concurrently.
- CEBAF uses this technology with electrons.
- Project X would add a bunch-by-bunch chopper to this scheme
 - Enhancement: supports variable bunch patterns





Figure 1: Schematic illustration of the CEBAF 12 GeV Upgrade.



Reference Design Provisional Siting




Pulsed 3-8 GeV Linac based on ILC / XFEL technology



Reference design: scope

- Warm cw front end 162.5 MHz, 5 mA (H- ion source, RFQ, MEBT, chopper)
- 3-GeV cw SCRF linac (325, 650 MHz), 1-mA ave. beam current
- Transverse beam splitter for 3-GeV experiments
- 3-8 GeV: pulsed linac (5% duty cycle), 1.3 GHz
- Recycler and MI upgrades
- Various beam transport lines







Linac beam current

- Linac beam current has a periodic time structure (at 10 Hz) with two major components.

Pulsed dipole

Beam current, mA





Chopping and splitting for 3-GeV experiments



1 μ sec period at 3 GeV




Muon pulses (16e7)	81.25 MHz, 100 nsec at 1 MHz	700 kW
Kaon pulses (16e7)	20.3 MHz	1540 kW
Nuclear pulses (16e7)	10.15 MHz	770 kW

Ion source and RFQ operate at 4.2 mA
75% of bunches are chopped at 2.5 MeV after RFQ








Beam after splitter





MEBT design: 5 mA at 162.5 MHz beam

TraceWin - CEA/DSM/Ifu/SACM




325 MHz warm bunching cavities

$$\varepsilon_{\perp} = 0.25 \pi \cdot \mu\text{m}; \quad \varepsilon_{z,n} = 0.3 \pi \cdot \mu\text{m}$$




SRF Linac Technology Map



Section	Freq	Energy (MeV)	Cav/mag/CM	Type
SSR0 ($\beta_G=0.11$)	325	2.5-10	18 /18/1	SSR, solenoid
SSR1 ($\beta_G=0.22$)	325	10-42	20/20/ 2	SSR, solenoid
SSR2 ($\beta_G=0.4$)	325	42-160	40/20/4	SSR, solenoid
LB 650 ($\beta_G=0.61$)	650	160-460	36 /24/6	5-cell elliptical, doublet
HB 650 ($\beta_G=0.9$)	650	460-3000	160/40/20	5-cell elliptical, doublet
ILC 1.3 ($\beta_G=1.0$)	1300	3000-8000	224 /28 /28	9-cell elliptical, quad





325 MHz spoke cavity families



SSR0 –
design,
prototyping



SSR1 – prototyping,
testing




SSR2 -
design

Parameters of the single-spoke cavities

cavity type	β_G	Freq MHz	$U_{acc, max}$ MeV	E_{max} MV/m	B_{max} mT	R/Q, Ω	G, Ω	* $Q_{0,2K}$ $\times 10^9$	$P_{max,2K}$ W
SSR0	$\beta=0.114$	325	0.6	32	39	108	50	6.5	0.5
SSR1	$\beta=0.215$	325	1.47	28	43	242	84	11.0	0.8
SSR2	$\beta=0.42$	325	3.34	32	60	292	109	13.0	2.9



Focusing Periods in SSR sections:




Focusing Period:

SSR0: (sol+cav) = 610 mm

SSR1: (sol+cav) = 800 mm

SSR2: (sol+cav+cav+60 mm) = 1600 mm


650 cavities




- 650 MHz, 5-cell cavity:
 - Similar length as for ILC-type cavity;
 - About the same maximal energy gain per cavity;
 - The same power requirements;
- Benefits compared to 1.3 GHz ILC-type cavity:
 - Higher accelerating efficiency → smaller number of cavities and RF sources;
 - Beam dynamics
 - 2-fold frequency jump instead of 4-fold → easier transition
 - Smaller beam losses;
 - Less effect of cavity focusing ($\sim 1/\lambda$)
- Trade-offs:
 - more serious problem with microphonics, but still may be manageable;
 - Larger diameter (comp to 1.3), higher cost per cavity;
 - additional rf frequency -> infrastructure.



650 MHz cavities



650 MHz: $\beta=0.61$




650 MHz: $\beta=0.9$


Parameter		LE650	HE650	
β_{geom}		0.61	0.9	
R/Q	Ohm	378	638	
G-factor, Ohm		191	255	
Max. Gain/cavity (on crest)	MeV	11.7	19.3	
Acc. Gradient	MV/m	16.6	18.7	
Max surf. electric field	MV/m	37.5	37.3	
Max surf. magnetic field,	mT	70	70	
$Q_0 @ 2^\circ K$	$\times 10^{10}$	1.5	2.0	
$P_{2K} \text{ max}$	[W]	24	29	



LE Cryomodules




HE Cryomodules



CMs lengths are shown from the first cavity iris to the last cavity iris.




650 MHz Cryomodule (Tesla Style-Stand Alone, 250 W @ 2K)







Cavity string & 300mm pipe





3 GeV CW Linac

Energy Gain per Cavity




- Based on 5-cell 650 MHz cavity
 - Crossover point ~450 - 500 MeV
- Single cavity per power source
 - Solid State, IOT



3 GeV CW Linac


Cryogenic Losses per Cavity




- ~42 kW cryogenic power at 4.5 K equivalent

3 – 8 GeV acceleration

- Pulsed linac based on the ILC technology
 - 1.3 GHz, 25 MV/m gradient, $\leq 5\%$ duty cycle
 - considering 1-30 ms pulse length
 - ~250 cavities (28 ILC-type cryomodules) needed.
 - Simple FODO lattice
 - 1 Klystron per 2 CM's



ILC







SRF Development Status

- 1300 MHz
 - 88 nine-cell cavities ordered
 - ~ 44 received (16 from U.S. industry, AES)
 - ~ 30 processed and tested, 8 dressed
 - 1 CM built (DESY kit) + second under construction (U.S. procured)
 - CM1 is now cold and about to initiate rf testing
 - 650 MHz
 - MOU signed with Jlab for 2 single cell $\beta = 0.6$ cavities
 - Order for six $\beta = 0.9$ single cell cavities in industry
 - 325 MHz
 - 2 SSR1 $\beta = 0.22$ cavities (Roark, Zannon) both VTS tested
 - 1 SSR1 dressed and under test at STF
 - 2 SSR1 being fabricated in India
 - 10 SSR1 ordered from Industry (Roark)
 - Design work started on 325 and 650 MHz CM
-



SRF Development 325 MHz



- SSR1 ($\beta=0.22$) cavity under development
 - Two prototypes assembled and tested
 - Both meet Project X specification at 2 K
- Preliminary designs for SSR0 and SSR2



Collaboration

- A multi-institutional collaboration has been established to execute the Project X RD&D Program.
 - Organized as a “national project with international participation”
 - Fermilab as lead laboratory
 - International participation via in-kind contributions, established through bi-lateral MOUs.
 - Collaboration MOUs for the RD&D phase outlines basic goals, and the means of organizing and executing the work. Signatories:

ANL	ILC/ART	RRCAT/Indore
BARC/Mumbai	IUAC/Delhi	SLAC
BNL	LBNL	TJNAF
Cornell	ORNL/SNS	VECC/Kolkata
Fermilab	MSU	
- It would be natural for collaborators to continue their areas of responsibility into the construction phase.



R&D Program

- The primary elements of the R&D program include:
 - Development of a wide-band chopper
 - Capable of removing bunches in arbitrary patterns at a 162.5 MHz bunch rate
 - Development of an H- injection system
 - Require between 4.4 – 26 msec injection period, depending on pulsed linac operating scenario
 - Superconducting rf development
 - Includes six different cavity types at three different frequencies
 - Emphasis is on Q_0 , rather than high gradient
 - Typically $1.5E10$, 15 MV/m (CW)
 - $1.0E10$, 25 MV/m (pulsed)
 - Includes development of qualified partners
 - Goal is to complete R&D phase by 2015
-



Summary

- Project X is central to Fermilab's strategy for development of the accelerator complex over the coming decade
 - World leading programs in neutrinos and rare processes;
 - Potential applications beyond elementary particle physics;
 - Technology aligned with ILC, Muon Accelerators, and Nuclear Energy
- Project X design concept is well developed and well aligned with the requirements of the physics program:
 - 3 GeV CW linac operating at 1 mA: 3 MW beam power
 - 3-8 GeV pulsed linac injecting into the Recycler/Main Injector complex
- We are expecting CD-0 for Project X in early 2011
- Project X could be constructed over the period ~2016 – 2020