



# **Project X H<sup>-</sup> Ion Source Acceptance Test and Future Plan**


Qing Ji

Lawrence Berkeley National Laboratory

May 19, 2011

**LAWRENCE BERKELEY NATIONAL LABORATORY**

# Project X Ion Source



- **D-Pace Filament driven H<sup>-</sup> source**
  - cw operation, up to 15 mA
  - No Cs
- **Plans for acceptance test**
  - Verify beam current
  - Emittance measurement
  - Beam stability
  - e/H<sup>-</sup> ratio



# H<sup>-</sup> Ion Source Acceptance Test



- May 9 – 13, 2011
- Participants:
  - Gabriel Cojocaru (TRIUMF)
  - Keerthi Jayamanna (TRIUMF)
  - Thomas Stewart (D-Pace)
  - Lionel Prost (FNAL)
  - Qing Ji (LBNL)


LAWRENCE BERKELEY NATIONAL LABORATORY



# H<sup>-</sup> Ion Source Factory Acceptance Test

- **The H- ion source was manufactured and assembled in the machine shop (Buckley Systems Ltd., Auckland, New Zealand) and passed the Factory Acceptance Test before shipped to TRIUMF.**
  - Vacuum leak testing of entire assembly
  - Electrical isolation test
  - Verification of the magnetic fields in the Ion Source Body, Back Plate and Extraction Lens
  - XY Steering Magnet: electrical isolation, temperature and voltage, magnetic field direction tests and magnet current and magnetic flux densities.
  - Cooling water flow rate test

# Ion Source Electrical Isolation Test



## Electrical Isolation Test Measurements

Record Resistance ( $\Omega$ )	Vacuum Box	Plasma Lens	Extraction Lens	Back Plate	Filaments
<b>Ion Source Body</b>	>500M $\Omega$	>500M $\Omega$	>500M $\Omega$	Not Electrically Isolated	>500M $\Omega$
<b>Filaments</b>	>500M $\Omega$	>500M $\Omega$	>500M $\Omega$	>500M $\Omega$	
<b>Back Plate</b>	>500M $\Omega$	>500M $\Omega$	>500M $\Omega$		
<b>Extraction Lens</b>	>500M $\Omega$	>500M $\Omega$			
<b>Plasma Lens</b>	>500M $\Omega$				



# Verification of Magnetic Fields

**Ion Source Body Field Verification Chart**

Magnet Row	Center of Ion Source Body Polarity	Maximum/Minimum Field at Center of Ion Source Body (kG)	Extraction End Polarity	Maximum/Minimum Field at Extraction End (kG)
1	-	-3.101	-	-2.097
2		0		0
3	+	+3.142	+	+2.165
4		0		0
5	-	-3.115	-	-2.046
6		0	-	-1.918
7	+	+2.941	-	-1.716
8		0	-	-1.851
9	-	-3.114	-	-1.910
10		0		0
11	+	+2.987	+	+2.107
12		0		0
13	-	-2.926	-	-2.096
14		0		0
15	+	+2.930	+	+1.938
16		0	+	+1.877
17	-	-2.928	+	+1.746
18		0	+	+1.845
19	+	+3.058	+	+1.938
20		0		0

**Back Plate Field Verification Chart**

Row	Polarity	Max Field (kG)
1	+	+2.156
2	-	-2.218
3	+	+2.218
4	-	-2.156


**Extraction Lens Field Verification Chart**

Side	Polarity	Max Field (kG)
Upstream	+	+0.2384
Downstream	-	-0.2362



# Axial Magnetic Field Verification

Magnetic Field (Bz) vs. Axial Position ( $\lambda$ )




LAWRENCE BERKELEY NATIONAL LABORATORY




# X-Y Steering magnetic Field Test

## X-Steering Magnetic Flux Density vs. Current




## Y-Steering Magnetic Flux Density vs. Current



LAWRENCE BERKELEY NATIONAL LABORATORY



# Ion Source Cooling Water Flow Test



Circuit	Inlet Pressure (psig)	Flow (L/min)
<b>Source Body</b>	62	23
<b>Filament</b>	62	1.6
<b>Back Plate</b>	62	18
<b>Plasma Lens</b>	62	11
<b>Extraction Lens</b>	62	10
<b>Steering Magnet</b>	62	11

LAWRENCE BERKELEY NATIONAL LABORATORY




# Ion Source Arrived at TRIUMF on May 9, 2011




LAWRENCE BERKELEY NATIONAL LABORATORY

# Ion Source Inspection



# Ion Source Installed on the Test Stand



LAWRENCE BERKELEY NATIONAL LABORATORY






# Beam Tests Activities


- **Beam tests at TRIUMF (May 10, 2011 – May 13, 2011)**
  - May 10: Ion Source has been pumped down sufficiently. Turn on cooling water, H<sub>2</sub> gas, and power supplies. No vacuum leak. Ramp up the power supplies slowly to “condition” the new filament and other HV components. Slowly increase the H- beam current from 1mA to 10mA.
  - May 11: Turn the beam, record all the parameters and take emittance scan from 1mA to 10mA, at 28keV and 20keV. Beam stability test at 5mA level at 28keV for two hours.
  - May 12: Turn the beam, record all the parameters and take emittance scan from 1mA to 10mA, at 30keV. Beam stability test at 10mA level at 28keV for over an hours.
  - May 13: Hands-on experience of source operation and tuning the beam at levels of 5mA and 10mA. Vent the system, take the ion source off the test stand, reassemble with the vacuum box. Pack and ready for shipping.



# Emittance Measurement – 10mA, 28keV




# Emittance Measurement – 5mA, 28keV




Parameter	Value
CURRENT	3.940e-03
	4.330e-02
VOLTAGE	9.4
	90.9
Y POSITION	7.0
	96.7
Z POSITION	92.6
WALLS	1.220e-01
	1.610e-01
	2.400e-01
	2.800e-01
	3.190e-01
	3.580e-01
	3.980e-01
	4.760e-01
	5.160e-01
	5.550e-01

4RMS emit= 47.53 $\pi$ mm-mm rad  
 2RMS size= 7.97 mm.  
 2RMS waist= 2.06 mm  
 waist loc= -0.3343 m.  
 2RMS div = 23.0 mrad.





# Emittance Measurement – 10mA, 20keV



Cartesian  
size<sup>2</sup>  
mrad<sup>2</sup>




5.850-03	13.7	99.8
9.490-02	7.9	91.1

4RMS emit = 114.05πmm-mrad  
2RMS size = 9.57 mm.  
2RMSwaist = 4.21 mm.  
waist loc = -0.3214 m.  
2RMS div = 27.1 mrad.





Normalized 4 rms emittance:  
~ 0.626  $\pi$  mm mrad

# Emittance Measurement – 5mA, 20keV




# Emittance Measurement – 10mA, 30keV






	Cart. value	11.7	100.0
	2rms	9.0	97.0
1. 52D-01	4.8	77.7	
2. 01D-01	3.7	80.6	
3. 50C-01	3.2	84.2	
4. 29C-01	2.9	85.5	
5. 48D-01	2.3	53.3	
3. 97D-01	1.7	42.1	
4. 46D-01	1.4	36.2	
5. 93D-01	0.8	22.7	
6. 42D-01	0.4	12.2	
6. 92D-01	0.1	2.9	

4RMS emit= 77.84 $\pi$ mm-mrad  
 2RMS size= 9.83 mm.  
 2RMSwaist= 2.90 mm  
 waist loc= -0.3500 m.  
 2RMS div = 26.8 mrad.




Normalized 4 rms emittance:  
 $\sim 0.565 \pi \text{ mm mrad}$

# Emittance Measurement – 5mA, 30keV






# Beam Stability Test (5mA level)




LAWRENCE BERKELEY NATIONAL LABORATORY

# Beam Stability @5mA: ~ +/- 1.9%






# Beam Stability Test (10mA level)



LAWRENCE BERKELEY NATIONAL LABORATORY

# Beam Stability @10mA: ~ +/- 0.4%






# Summary


- We didn't experience any vacuum leak nor water leak on the ion source assembly.
- After filament and voltage conditioning, the  $H^-$  ion beam currents from 1mA to 10mA have been verified. The highest detected in the Faraday cup was 10.53mA, which was limited by the capabilities of the power supplies in the test stand.
- Emittance were measured from beam level from 1mA to 10mA, at various beam energy. Normalized 4 rms emittance were less than  $0.63 \pi \text{ mm mrad}$ , which met the specification.
- Beam stability was tested at beam level of 5mA and 10mA for over an hour each. Without any feedback control loop, the beam current stability was better than  $+/- 2\%$ . The second beam stability test showed better results ( $< +/- 0.4\%$ ) after longer filament conditioning.
- $e/H^-$  ratio was not physically measured during the acceptance test due to the limitation of the hardware setup. Based on TRIUMF experience, the electrons co-extracted from the ion source are properly dumped to plasma and extraction electrodes. Electron beams reaching the Faraday cup are negligible

LAWRENCE BERKELEY NATIONAL LABORATORY



# Beam Current vs. Arc Power





# Normalized Emittance (4rms) vs. Beam current



# Plasma Electrode Parameters for Various Beam Output



# Extraction Electrode Parameters for Various Beam Output



Current on extraction electrode may include dumped electrons and H- beam with large angles.

# Clues of $e/H^-$ ratio?

Ref: T. Kuo et al, Rev. Sci. Instru., 67, 1314(1996).










FIG. 4. Performance of the 15 mA dc  $H^-$  source in terms of  $e/H^-$  ratio, emittance, and brightness.

LAWRENCE BERKELEY NATIONAL LABORATORY

# Bias Power Supply Parameters for Various Beam Output



# Plasma Electrode Bias Dependence





# Future Plan

- Near term:
  - LEBT beam dynamics study
    - Use the experimental data from acceptance tests to conduct end-to-end simulation on LEBT and RFQ
  - Ion Source
    - Setup of the ion source test stand at LBNL
    - Repeat the current and emittance measurement at LBNL
    - Optimization of the extraction system
- Long term:
  - LEBT design and beam test
    - Development of magnetic LEBT prototype incrementally
    - LEBT chopper and matching to RFQ
    - Beam testing