

# The Fermilab HINS Test Facility and Beam Measurements of the Ion Source and 325 MHz RFQ


V. Scarpine, B. Webber, J. Steimel, B. Hanna, C. Maag,  
S. Chaurize, S. Hays, D. Wildman  
Fermilab

Project X Weekly Meeting  
September 13, 2011

# Brief History of Meson Detector Building (HINS) Test Facility

- This thrust began in 2006 with initiation of the High Intensity Neutrino Source (HINS) program to demonstrate technology applications new to the low-energy front-end of a pulsed, high-intensity proton/H<sup>-</sup> Linac
- The plan *was* to construct a ten's of MeV Linac to demonstrate:
  - Beam acceleration using spoke-type superconducting RF (SRF) cavity structures starting at a beam energy of 10 MeV
  - High power RF vector modulators controlling multiple RF cavities driven by a single high power klystron for acceleration of a non-relativistic beam
  - Control of beam halo and emittance growth by the use of solenoid focusing optics
  - Fast, 325 MHz bunch-by-bunch, beam chopping
- Now plan is to demonstrate:
  - *High power RF vector modulators controlling multiple RF cavities driven by a single high power klystron for acceleration of a non-relativistic beam*
  - *Test facility for beam diagnostics and fast chopper (?)*

# MDB Test Facility Layout




# HINS Beam Parameters



	Proposed	Actual	
Particle	H+ then H-	H+ <i>then H-?</i>	
Nominal Bunch Frequency/Spacing	325 3.1	325 3.1	MHz nsec
Pulse Length	3 @ 2.5 Hz 1 @ 10 Hz	1 @ 0.2 Hz 0.1 @ 1 Hz	msec
Average Pulse Current	~ 20 (source)	~ 20 (H, 2H+, 3H+) ~8 (RFQ - H)	mA
Pulse Rep. Rate	2.5/10	0.2/1	Hz

# HINS Proton Source and LEBT



Duo-plasmatron Proton Source	
Energy	50 keV
Peak Current	> 20 mA
Pulse	3 msec
Rep. rate	2.5 Hz

	Name	Current [Amp]	B [Gauss]
SOL-U	Upstream solenoid	850	7900
SOL-D	Downstream solenoid	850	7900
DIP-UH	Upstream horizontal dipole	3	100
DIP-UV	Upstream vertical dipole	3	100
DIP-DH	Downstream horizontal dipole	3	100
DIP-DV	Downstream vertical dipole	3	100

# HINS LEBT Beam Measurement Setup




Proton  
Source




Toroid

Focusing  
Solenoids

Wire  
Scanner




# A Typical Wire Scan




Signal with background subtracted.



The time structure of a 100  $\mu$ s pulse. The flattop is about 50  $\mu$ s.

# Proton Source Slit-WS Emittance Measurement



# Proton Source Slit-WS Emittance Measurement





## Source Species

Green – Source Extractor Voltage

Yellow – LEBT Toroid Current

Red – Straight ahead Faraday Cup

Blue – Spectrometer Faraday Cup (bend)

- Downstream solenoid optimized for each species
- Upstream solenoid fixed at 470 A


**~ 40% Protons**

**~ 30%  $H_2^+$**


**~ 30%  $H_3^+$**

**• As measured by LEBT toroid**

# Phase Space Signal Cleaning



# Source Emittance Slit & Solenoid Scans





# Initial RFQ Beam Measurements



## RFQ design:

- 2.5 MeV
- 325 MHz
- Peak power up to 450 kW
- 1 ms pulses at 10 Hz

**RFQ suffered from detuning problems and water leaks → 50 μs pulses at 1 Hz**




## Profile Sigmas and Integrals ; I ~ 4 mA

Sigmas	Horizontal	Vertical	Diagonal
Scanner 1	4.5 mm	4.2 mm	4.3 mm
Scanner 2	7.0 mm	6.8 mm	6.2 mm
Scanner 3	16.2 mm	13.2 mm	13.4 mm

Integrals	Horizontal	Vertical	Diagonal
Scanner 1	14.8 V*mm	14.9 V*mm	14.7 V*mm
Scanner 2	11.8 V*mm	10.5 V*mm	10.2 V*mm
Scanner 3	11.6 V*mm	10.1 V*mm	10.7 V*mm

**Beam loss after first wire scanner → need focusing**

# RFQ Energy Measurement by Time of Flight



Signals from toroid and two BPM buttons, all downstream of the RFQ


Upper display: 2  $\mu$ sec/div

Lower display: 20 nsec/div

Lower display shows the 44 ns delay expected for transit of 2.5 MeV beam between the BPM two buttons separated by 0.96 meters


Beam current is about 3 mA

# RFQ Stability




Phase variation from time-of-flight

Energy Stability



Relative RFQ output beam vs. RF Power



# Next Iteration of RFQ Beam Measurements




- Initial measurements suffered from RFQ water leak problems
  - RFQ limited to 50  $\mu$ sec pulses
  - RFQ has been repaired and reinstalled at the Meson test facility
- Initial RFQ measurements suffered many issues
  - No transverse focusing → **Quadrupoles added**
  - No longitudinal measurements → **FFC and BSM**
  - No transverse emittance measurements → **Quad-Wire, Slit-Wire**
  - Energy measurement was not precise → **Spectrometer magnet**
  - RFQ efficiency not accurately measured → **Toroid at RFQ output**
- New diagnostics line has been install
  - Reconfigurable, movable
  - ***Space available for R&D projects***


# Advanced HINS Diagnostics Line



T: Toroid  
GV: Gate Value  
Q: Quadrupole  
BPM: Beam Position Monitor  
WS: Wire Scanner  
S: Horz and Vert Slits  
BSM: Bunch Shape Monitor (Longitudinal)  
FFC: Fast Faraday Cup  
FD: Faraday Cup/Dump  
SM: Spectrometer Magnet

RFQ Beam  
Diagnostics  
April 2011






# Transverse Emittance from Quadrupole Scans



Horizontal Quad scan and fit




the equation is  $\sigma = .05452 - .01034k + 5.02791E-4k^2$   
 setting the derivative to zero gives  $k_0 = 10.283$ . Note this is the gradient at minimum

**Unnormalized emittance**


- 6 mA RFQ beam
- 100 usec pulses

**H: 1.49 pi mm-mrad**

**V: 1.88 pi mm-mrad**



# Un-normalized Emittance along 500 usec Pulse – Quad Scan




# Phase Space Plots; 9 mA RFQ




H  
O  
R  
I  
Z  
O  
N  
T  
A  
L

V  
E  
R  
T  
I  
C  
A  
L


Horz Phase Space; 9 mA




Vert Phase Space; 9 mA




Horz Phase Space; 9 mA



Vert Phase Space; 9 mA



# Horizontal Phase Space along Pulse - Preliminary





- X – X' along beam pulse; arbitrary units
- 6 mA beam

# Odd Transverse Shape Effects





Vertical

Horizontal




Front of pulse



Back of pulse

Halo?

Main beam




Horz Slit

# Horz Shape at Minimum Focus at Wirescanner



Beginning of 100 usec pulse


Middle of 100 usec pulse




Background?

Background?

# Longitudinal Bunch Shape Monitor



*FWHM: (prelim)*  
*~ 40° @325 MHz*  
*~ 340 ps*






Translate time coordinate into space coordinate using RF deflector cavity

- like a streak camera

Systematics need to be understood for H- at low energy



# Longitudinal Bunch Shape – Fast Faraday Cup




# Longitudinal Shape VS RFQ Power



Feed fast Faraday Cup into high bandwidth scope to measure bunch shape.





# Bunch Shape Along Pulse



Fit individual bunches along pulse

- RFQ at 300 KW
- Histogram  $\rightarrow$   $\sim 0.28$  ns sigma
- $\rightarrow$  33 deg @ 325 MHz
- Need to deconvolve cable



# Beam Diagnostic Projects for Project X

## Transverse Diagnostics

- Laser Transverse Profile Monitor\*
- Ionization Profile Monitors
- Electron Wire Transverse Profile Monitor – with SNS

## Longitudinal Diagnostics

- Wire Longitudinal Profile Monitor\*
- Laser Longitudinal Profile Monitor\* - with LBNL
- Broadband Faraday-cup – with SNS\*

## Halo Monitoring – transverse and longitudinal


- Vibrating wire\* - from Bergoz Instrumentation
- Laser wire\* - with LBNL

## MEBT Emittance station


- Slit-collector\*
- Laser Slit\*

\* Project X related instrumentation to be tested at HINS

See R. Wilcox Poster TUPD53  
“A Low-Power Laser Wire with Fiber Optic Distribution”



Laser Wire Emittance Station



# Conclusion



- MDB Test Facility (HINS) has taken initial proton source and RFQ beam measurements
- RFQ has been repaired and reinstalled at MDB
- New diagnostics line has been installed
- RFQ Beam measurements have been made – *analysis proceeding*
- Six cavity being installed now – accelerator and buncher cavities
  - Beam by early Sept
  - *H<sup>-</sup> to be installed later this year?*
- The MDB test facility HINS can play a role in Project X front-end testing
  - R&D for beam diagnostics and beam chopper
  - Outside collaborators to participate in diagnostics development

The End