

Project X: Introduction, Strategy, and Collaboration Meeting Goals

Steve Holmes

Project X Collaboration Meeting
November 21, 2008

Outline



-
- Strategic Context
 - Project X Goals and Initial Configuration
 - Project X Research, Design, and Development Plan
 - Relationship of Project X to other Programs
 - Meeting Goals, Agenda, and Organization


Project X website: <http://projectx.fnal.gov/>

Strategic Context

Fermilab Long Range Plan



- Fermilab is the sole remaining U.S. laboratory providing facilities in support of accelerator-based Elementary Particle Physics.
- The Fermilab long-term strategy is fully aligned with the P5 plan:
 - Energy and intensity frontiers share strong reliance on accelerators



Strategic Context

P5 Recommendations



- Energy Frontier
 - “The panel recommends for the near future a broad accelerator and detector R&D program for lepton colliders that includes continued R&D on ILC ... in support of the international effort.”
 - “The panel also recommends R&D for alternative accelerator technologies, to permit an informed choice when the lepton collider energy is established.”
- Intensity Frontier
 - “The panel recommends an R&D program in the immediate future to design a multi-megawatt proton source at Fermilab and a neutrino beamline to DUSEL...”
 - “The panel further recommends that in any funding scenario considered by the panel Fermilab proceed with the upgrade of the present proton source by about a factor of two, to 700 kilowatts...”

Strategic Context

Evolution of the Accelerator Complex



- Energy Frontier
 - Tevatron → ILC or Muon Collider as options for the Fermilab site
- Intensity Frontier
 - NuMI → NOvA → very long baseline/mu2e → multi-MW Proton Source
 - Initial stages supported by ANU (NOvA): 700 kW
- Fermilab view: An effective implementation of a multi-MW proton facility would be based on a superconducting 8 GeV linac
 - Alignment with ILC technology development
 - Flexibility for the future
 - aka “Project X”

Project X Initial Configuration

Mission Need



- The P5 report identifies mission need based on:
 - **A neutrino beam for long baseline neutrino oscillation experiments.**

A new 2 megawatt proton source with proton energies between 50 and 120 GeV would produce intense neutrino beams, directed toward a large detector located in a distant underground laboratory.
 - **Kaon and muon based precision experiments exploiting 8 GeV protons from Fermilab's Recycler, running simultaneously with the neutrino program.**


These could include a world leading muon-to-electron conversion experiment and world leading rare kaon decay experiments.
 - **A path toward a muon source for a possible future neutrino factory and, potentially, a muon collider at the Energy Frontier.**

This path requires that the new 8 GeV proton source have significant upgrade potential.


Project X Initial Configuration



- Project X Design Criteria
 - 2 MW of beam power over the range 60 – 120 GeV;
 - Simultaneous with at least 150 kW of beam power at 8 GeV;
 - Compatibility with future upgrades to 2-4 MW at 8 GeV



Project X Initial Configuration Provisional Siting



Project X Facility Overview

High Level Performance Goals



Linac

Particle Type	H ⁻	
Beam Kinetic Energy	8.0	GeV
Particles per pulse	1.6×10^{14}	
Linac pulse rate	5	Hz
Beam Power	280-1000	kW

Recycler

Particle Type	protons	
Beam Kinetic Energy	8.0	GeV
Cycle time	1.4	sec
Particles per cycle to MI	1.6×10^{14}	
Particles per cycle to 8 GeV program	1.6×10^{14}	
Beam Power to 8 GeV program	140-860	kW

Initially:

- 2 linac beam pulses/1.4 seconds
- Remaining (5) pulses available for
 - Maintain 2 MW down to 60 GeV
 - Future upgrades
 - Diagnostics

Main Injector

Beam Kinetic Energy (maximum)	120	GeV
Cycle time	1.4	sec
Particles per cycle	1.7×10^{14}	
Beam Power at 120 GeV	2100	kW

Project X RD&D Plan



-
- The primary goal of the Research, Design, and Development (RD&D) program is to support Critical Decision 2 in 2012, leading to a 2013 construction start.
 - Design and technical component development;
 - Fully developed baseline scope, cost estimate, and schedule;
 - Formation of a multi-institutional collaboration capable of executing both the RD&D plan and the follow-on construction project.
 - **Secondary goals:**
 - Coordination of Project X and ILC scrf programs to provide maximal benefit to each;
 - Retain alignment of Project X and the Neutrino Factory and Muon Collider programs to assure that Project X could serve as a stepping stone to either facility.

Project X RD&D Plan

Near-term Strategy



- Develop an Initial Configuration Document
 - Meeting the design criteria and program goals
 - ICD subject to configuration control
 - ⇒ Released 10/31: available at <http://projectx.fnal.gov/>
- Revise/update the current RD&D Plan
 - Based on the ICD
 - Review existing plan to emphasize reduction of risk
 - ⇒ In process, collaboration input at the November Collaboration Meeting
- Create a preliminary cost estimate
 - Based on the ICD
 - ⇒ In process, available early 2009

Project X RD&D Plan

Near-term Strategy



- Establish a multi-institutional collaboration for the RD&D phase
 - Fermilab holds overall responsibility as host laboratory;
 - Achieve maximal alignment with institutional expertise and experience;
 - Recognize it would be natural for responsibilities to carry over into the construction phase.
- CD-0 in FY2009
 - Requires independent review because (we suspect) >\$750M
 - Coordinated with very long baseline (DUSEL) and mu2e
 - Based on: ICD, preliminary cost estimate, P5 mission definition
- It is anticipated that the DOE laboratories will be supported on a continuing resolution through (at least) the first half of FY2009.
 - This will limit our ability to initiate a comprehensive R&D program early in the year.

Project X RD&D Plan

Working Timeline (technically limited)



- FY2009
 - Complete Initial Configuration Document (ICD)
 - Develop Upgrade Concept for 2-4 MW at 8 GeV
 - Form RD&D Collaboration
 - Establish Project Management team
 - Revise RD&D plan and initiate work
 - Complete a preliminary cost estimate based on the ICD
 - Complete Mission Needs Statement and Mission Need Independent Review
 - Receive CD-0
 - Request PED funds for FY2011
 - Initiate work on Conceptual Design Report
 - Develop NEPA strategy
- ⇒ This can largely be accomplished under the FY09 (half-year) CR
-

Project X RD&D Plan

Working Timeline (technically limited)



- FY2010
 - Alternative implementations studies
 - Initiate Environmental Assessment
 - Initiate permitting documentation
 - Draft of all CD-1 documentation, including CDR
- FY2011
 - CD-1
- FY2012
 - CD-2/3a
- FY2013
 - CD-3
- ~FY2013~2017
 - Construct



Project X RD&D Plan

Alternative Designs



- Consideration of alternative designs is mandated by DOE 413.3 in advance of CD-1.
- Initial thinking on alternatives has begun
 - Current primary alternative is a hybrid linac/synchrotron
- Process
 - Intention is to carry through CD-0 based on the ICD and accompanying cost estimate
 - In series develop alternative configuration (ACD) and then produce cost estimate that can be used as basis for an alternatives study.
 - Utilizing same teams
- I have asked the Working Group Leaders to focus discussion in this meeting on the ICD
 - 90% of technology in the ICD would likely be common to an alternative configuration.

Relationship to Other Programs: Linac Technology



Relationship to Other Programs: ILC/SRF Joint Development Strategy



- 38 ILC-like cryomodules are required for Project X. In detail they will not be identical to ILC:
 - Gradient: 25 MV/m
 - Beam current: 20 mA × 1.25 msec × 5 Hz
 - Focusing: Quadrupole element required in each CM
 - Consistent with upgrade path
 - 1.25 → 2.5 msec pulse length
 - 5 → 10 Hz pulse rate
- } 4 MW at 8 GeV
- Close coordination between Project X and GDE/ART during development phase
 - Strategy based on ILC “plug compatibility”
 - Retain ILC cavity spacing and primary interface dimensions
 - Cryomodule development is through the ILC program
 - CAF and ILCTA-NML are constructed via the SRF program: 1 CM/month assembly capability and beam testing of a complete rf unit

Relationship to Other Programs: ILC/SRF Joint Development Strategy



- Industrialization

- Production of 38 ILC-like (plus 8 $\beta=0.8$) CMs over a 2-3 year period is consistent with CAF capabilities in ~2013; however, the production rate remains well below that required by ILC

⇒ This activity could represent the initial phase of an industrialization buildup for ILC (in the U.S.).



Relationship to Other Programs: ILC/SRF Joint Development Strategy




- Other opportunities:
 - E-cloud studies and simulations, including participation in CESR TA
 - RF power generation, distribution, controls, and diagnostics share many features in common.
 - Conventional facilities designs provide opportunities for common solutions.
 - ILCTA_NML rf unit test will fulfill many of the requirements of S2, and will be available for studies with both PX and ILC beam current parameters.
 - Construction and operational experience with Project X will be invaluable in planning/executing ILC (if PX were to precede ILC, ditto for XFEL)
- ⇒ Essentially all these efforts are using shared (people) resources.

Relationship to Other Programs: HINS Joint Development Strategy



- The HINS program is developing front end technology beyond the requirements of Project X initial goals:
 - 60 MeV front end @ 27 mA × 1 msec × 10 Hz
 - Demonstrate novel technologies for a high intensity non-relativistic linac
 - Multiple room temperature and sc cavities driven by a single rf source (high power vector modulators)
 - High speed (nsec) beam chopping at 2.5 MeV
 - Establish technical feasibility and cost basis by ~2011
 - Integrate into Project X R&D effort at time of CD-0



Project X RD&D Plan

Integrated SRF Plan



	FY08	FY09	FY10	FY11	FY12	FY13
ILC C+CM	CM1	CM2		CM3 (Type IV)	CM4 (PX)	
						rf unit sys tst
ILC RF Power		MBK	PFN modulator			
SRF Infra.					NML complete	CAF complete (1 CM/month)
HINS					60 MeV beam tests	
Project X		CDR		FE decision Final gradient decision		rf unit sys tst

Relationship to Other Programs: Muons




- Project X shares many features with the proton driver required for a Neutrino Factory or Muon Collider
 - IDS-NF shows 4 MW @ 10 ± 5 GeV proton energy
 - Muon Collider requires similar power, but requires charge consolidated into a single bunch
- Natural evolutionary schemes through neutrino superbeams:
NO ν A → Very Long Baseline → Neutrino Factory → Muon Collider
 - (see P5 presentations by Y-K. Kim and R. Palmer)

Relationship to Other Programs: Muons: Possible Evolution (Palmer/P5)



A Phased Approach



18

Project X RD&D Plan

Muon Facilities Joint Development Strategy



- Develop upgrade concept for the Project X linac aimed at 2-4 MW
⇒ The ICD includes such a concept (up to 4 MW)
- Develop a performance specification for a Proton Driver supporting a Neutrino Factory and Muon Collider, consistent with Project X concepts.
 - Issues: Average beam power, repetition rate, particles/bunch, bunch intensity
 - These issues are likely to require a new storage ring downstream of the linac.
- Develop a conceptual design for the NF/MC Proton Driver based on Project X linac and downstream accumulation/packaging ring(s).
- Coordinate with NFMCC, MCTF, and IDS_NF

Project X RD&D Plan

Collaboration Plan



- The intention is to organize and execute the RD&D Program via a multi-institutional collaboration.
 - Goal is to assign collaborators complete sub-projects ⇒ responsibility for design, engineering, cost estimating, and potentially construction if/when Project X proceeds.
 - Project X R&D Collaboration to be established via a Collaboration Memorandum of Understanding (MOU) outlining basic goals of the collaboration, and the means of organizing and executing the work.
 - It is anticipated that the Project X RD&D Program will be undertaken as a “national project with international participation”. Expectation is that international participation would largely be via in-kind contributions, established via bi-lateral MOUs.
 - International participation in the Collaboration Meeting to identify areas of common interest.

Project X RD&D Plan

Collaboration Plan



- A draft MOU covering the period through CD-2 is currently circulating for comment among the following potential U.S. laboratory collaborators:
 - ANL
 - BNL
 - Cornell
 - LBNL
 - ORNL/SNS
 - MSU
 - TJNAF
 - SLAC
 - ILC/GDE/ART
- Hope to finalize the MOU at this Collaboration Meeting

Project X Collaboration Meeting: Goals



- Form the RD&D Collaboration
 - Finalize the Collaboration MOU;
 - Initial meeting of Collaboration Council (see subsequent discussion);
 - Initial discussions with potential international and university collaborators on possible interests and modes of participation.
 - Confirm initial performance goals and configuration
 - Review, understand, and suggest downstream modifications to the ICD.
 - Establish the RD&D plan
 - Review, understand, and update as necessary the RD&D plan;
 - Establish initial institutional areas of responsibility;
 - Define deliverables and work plan for FY2009-10;
 - Understand the integration with the ILC and SRF infrastructure programs.
-

Project X Collaboration Meeting: Agenda



- Friday, November 21
 - Opening plenary session 08:30-10:30
 - Project X Introduction and Strategy Steve H.
 - Project X Initial Configuration Overview Paul D.
 - Coffee Break (1 West) 10:30-11:00
 - Working Groups session one 11:00-12:30
 - Lunch (self-serve) 12:30-13:30
 - Working Groups session two 13:30-15:30
 - Coffee Break (WH2, W&C) 15:30-16:00
 - Working Groups session three 16:00-17:30
 - Collaboration Council meeting 17:00-18:00
 - Adjourn 17:30

Project X Collaboration Meeting: Agenda



- Saturday, November 22
 - Working Group Reports 08:30-10:00
 - Linac
 - SRF Technologies
 - Cryogenics
 - Coffee Break 10:00-10:30
 - Working Group Reports 10:30-12:00
 - Instrumentation
 - Main Injector
 - Beam Transfer Line/Recycler
 - Adjourn 12:00
 - Lunch not available in the Cafeteria after 12:00

Project X Collaboration Meeting: Working Groups



- Charge to the working groups:
 - Discuss and propose any potential modification to the ICD;
 - Identify issues that need to be addressed within the RD&D program;
 - Propose timeline (RD&D plan components and sequencing);
 - Propose a provisional distribution of responsibility through CD-1;
 - Identify any issues related to the above that need resolution

Project X Collaboration Meeting: Working Groups



- Linac S. Nagaitsev/P. Ostroumov
 - Beam dynamics
 - Configuration (includes rf power generation and distribution)
- Main Injector I. Kourbanis/T. Roser
- Beam Transfer Line/
Recycler D. Johnson/D. Raparia
- SRF technology R. Kephart/G. Apollinari/R. Rimmer
 - Cavities, cryomodules, infrastructure
- Instrumentation M. Wendt/W. Blokland
- Cryogenic Systems A. Klebaner/ D. Arenius

Project X Collaboration Meeting: Collaboration Council



Collaboration Council Meeting Agenda

1. Discussion of working arrangements under the MOU
2. Discussion/finalization of the MOU
3. Management Strategy
4. Role of the Collaboration Council
5. Review of provisional institutional assignments
6. Desired meeting frequency

Summary



- Project X is central to Fermilab's strategy for the future:
 - Energy Frontier: Aligned with ILC technology development; preserves Fermilab as potential site for ILC or a Muon Collider
 - Intensity Frontier: Support a world leading very long baseline neutrino and rare processes programs; preserves Fermilab as potential site for a Neutrino Factory
 - An initial configuration has been established meeting requirements as specified in the P5 report
 - >2 MW at 60-120 GeV, simultaneous with >600 kW at 8 GeV
 - The initial configuration can be upgraded to 2-4 MW at 8 GeV
 - Project X RD&D plan developed (through CD-2)
 - Integrates effort on Project X, ILC, SRF, and HINS
 - Collaboration being formed
- ⇒ We need everyone's help to carry this forward**

Working Group Room Assignments



Linac	1 West (WH1W) Curia II 4:00 – 5:30
Main Injector	Comitium (WH2SE)
Beam Transfer Line/Recycler	Snakepit (WH2NE)
SRF Technology Development	Racetrack (WH7N)
Instrumentation	Curia II (WH2SW)
Cryogenic Systems	Black Hole (WH2NW)
Collaboration Council	1 North (WH1N)