

High Power RF Systems for  
2-8 GeV Fast Cycling Synchrotron  
PROJECT X (ICD-2)

**John Reid**

**September 11 , 2009**

# Scope

---

---

- **Summary of RF System Parameters**
- **Diagram of proposed RF Cavity -Fundamental**
- **High level components**
- **2<sup>nd</sup> Harmonic**
- **R&D**
- **Cost**
- **Conclusion**







# RF Parameters

Energy	2 to 8	GeV
Transition Energy	13.36	GeV
Number of Particles	$2.67 \times 10^{13}$	
Beam Current @ injection	2.2	Amps
Repetition rate	10	Hz
Acceleration Ramp Slope	165	GeV/s
Frequency Min	50.33	MHz
Frequency Max	52.81	MHz
Frequency sweep	2.5	MHz
Number of First Harmonic RF stations (h=98)	16	Stations
Peak accelerating voltage	1.6	MV
Cavity peak voltage	100	kV / cavity
Peak Power Dissipation Cavity	50	kW /cavity
Peak Power: beam + cavity	1.5	MW
Peak Power per cavity: beam + cavity	93.75	kW / cavity
Cavity Rs	100	k $\Omega$
Cavity Q	$\sim 2857$	
Cavity Rs/Q	$\sim 35$	
Cavity Tuner Geometry		Perpendicular Biased



# RF System Parameters



Beam and RF system parameters during acceleration.

Total rf power is presented for the case when 2 of 16 & 1 of 10 cavities are not operating



# Cavity Design


---

---

- Cavity is based on the SSC Low Energy Booster cavity which is a quarter wave cavity with low R/Q to reduce the effects of beam loading.
- Engineering challenge – to providing adequate cooling to the garnets in this design and have reliable operation at 100KV gradient.
- Each cavity is ~ 1.25 meters in length.




# Cavity Design




# Prototype Cavity




# Cavity Prototype



# Cavity Prototype




# Standard MI RF Cavity



As Viewed From Aisle Side

Present Main Injector Cavity

# Standard MI RF Cavity



# Fermilab Booster Cavity

---

---



# Typical Station Layout

---

---



# Possible Equipment Gallery Layout

---

---




# Series Tube Modulator



Standard MI Modulator



# Ferrite Bias Supply



- 35V, 2500A fast slewing power supply used for tuning the present Fermilab Booster rf cavity.
- Can operate at 15 Hz

# 8 KW Solid State Driver Amp

---

---



Present MI Solid State  
Driver Amplifier



# Power Amplifier

---

---



- Power Amp will be a modified version of our standard 150KW power amplifier.
- It will be cathode driven from a solid state amp located in the surface building
- Grid grounded for rf but biased to allow dynamic programming throughout the cycle.
- Grid, screen, filament supplies located in surface building



# Anode Power Supplies

---

---

- **Two large anode supplies will be required to power the fundamental rf system.**
- **Divided into two groups of 8 stations.**
- **Supplies will be very similar to the existing MI-60 anode supplies that presently power the MI's rf system.**
- **Each supply will consist of :**
  - Fused disconnect to the 13.8KV line
  - Fast step start vacuum circuit breaker,
  - 2MW main rectifying transformer,
  - Rectifier stack,
  - Interphase reactor,
  - Capacitor bank,
  - Crowbar,
  - Individual dc vacuum switches connecting each modulator to the anode supplies dc bus (8 station per supply).

# Anode Supplies at MI-60

---

---



# RF Controls

---

---

- **Much of the rf controls would be very similar to that of the present Main Injector's 53MHz system.**
- **This would include:**
  - Cavity tuning controller
  - Direct rf feedback
  - Feed forward
  - Possible comb filter

# Second Harmonic System

Frequency Min	100.66	MHz
Frequency Max	105.62	MHz
Frequency sweep	5.0	MHz
Number of second Harmonic RF stations (h=196)	10	Stations
Peak accelerating voltage	0.7	MV
Cavity peak voltage	70	kV / cavity
Peak Power Dissipation Cavity	24.5	kW /cavity
Peak Power: beam + cavity	0.43	MW
Peak Power per cavity: beam + cavity	43	kW / cavity
Cavity Rs	100	k $\Omega$
Cavity Q	2850	
Cavity Rs/Q	~35	
Cavity Tuner Geometry		Perpendicular Biased

# Second Harmonic

---

---

- **Cavity design could be similar to the fundamental including the use of perpendicular biased tuner arrangement.**
- **Specification calls for 2<sup>nd</sup> harmonic to track the fundamental through out the whole cycle.**
- **Frequency sweep = 5 MHz.**
- **If 2<sup>nd</sup> harmonic only needed at injection, cavity design would be much cheaper to fabricate.**

# R&D Program

---

---

- **Start R&D program with existing prototype cavity and tuner.**
- **Complete low level measurements to determine required modifications for our application.**
- **Implement design changes, especially cooling and power amplifier layout.**
- **Run in MI-60 test station to measure high power performance.**
- **Cost ~ \$ 5,000,000**

# Fundamental System Cost

DRAFT September 2009	Each			FTE	FTE	FTE	FTE	FTE
	M&S	Quantity	31,061,000	Labor	Labor	Labor	Labor	Labor
Fundamental 50.3-52.81MHz	M&S	Quantity	31,061,000	16.98	1.69	25.15	7.15	1.78
				EE	ME	ET	MT	DR
Series Tube Modulator	155,000	16	2,480,000	1.8	0	3.7	1	0.2
Ferrite Bias Power Supply	165,000	16	2,640,000	1.9	0.1	3.9	1	0.25
150 KW Power Amplifier	100,000	16	1,600,000	0.31	0.1	2.6	0.25	0
Anode Supplies	417,000	2	834,000	0.5	0.1	0.75	0.25	0.2
RF Cavity with Perpendicular Bias Tuner	650,000	16	10,400,000	1.5	1	3.7	3.7	0.5
Solid State Driver Amplifiers	150,000	16	2,400,000	1.2	0.15	3.4	0.25	0.1
RF Station Controls	35,000	16	560,000	1	0	2	0	0.1
Installation								
Cabling materials + termination	12,000	16	192,000					
Cable installation cost	5,000	16	80,000					
Cable Tray	55,000	1	55,000	0.05	0.05	0.1	0	0.05
High Current Ferrite Bias Tuner Bus	20,000	16	320,000	0.2	0.1	0.3	0.3	0.1
Utilities								
AC Power Distribution	250,000	1	250,000					
LCW Water System Local for Rf System	1,000,000	1	1,000,000					
Low Level RF								
Local Station VXI	500,000	1	500,000	4	0	2	0	0.1
Global LL Control System in control room	100,000	1	100,000	3	0	1	0	0.1
Long. Beam/ RF Diag	150,000	1	150,000	1	0	0.5	0	0
Test Station	1,500,000	1	1,500,000	0.52	0.09	1.2	0.4	0.08
Spare Parts	1,500,000	4	6,000,000					



# 2<sup>nd</sup> Harmonic System Cost

<b>DRAFT September 2009</b>					FTE	FTE	FTE	FTE	FTE
	Each				Labor	Labor	Labor	Labor	Labor
<b>Second Harmonic 100.6-105.62MHz</b>	<b>M&amp;S</b>	<b>Quantity</b>	<b>18,009,000</b>		<b>5.72</b>	<b>1.06</b>	<b>13.84</b>	<b>4.5</b>	<b>0.95</b>
Series Tube Modulator	155,000	10	1,550,000		1.1	0	2.3	0.6	0.1
Ferrite Bias Power Supply	165,000	10	1,650,000		1.2	0.06	2.4	0.6	0.15
150 KW Power Amplifier	100,000	10	1,000,000		0.2	0.06	1.6	0.15	0
Anode Supplies	417,000	2	834,000		0.26	0.05	0.4	0.12	0.1
RF Cavity with Perpendicular Bias Tuner	650,000	10	6,500,000		0.94	0.62	2.3	2.3	0.31
Solid State Driver Amplifiers	150,000	10	1,500,000		0.75	0.09	2.1	0.15	0.06
RF Station Controls	35,000	10	350,000		0.6	0	1.3	0	0.06
<b>Utilities</b>									
AC Power Distribution	100,000	1	100,000						
LCW Water System Local for Rf System	100,000	1	100,000						
<b>Installation</b>									
Cabling	12,000	10	120,000						
Cable installation cost	5,000	10	50,000						
Cable Tray	55,000	1	55,000		0.03	0.03	0.06	0	0.03
High Current Ferrite Bias Tuner Bus	20,000	10	200,000		0.12	0.06	0.18	0.18	0.06
<b>Test Station</b>	1,000,000	1	1,000,000		0.52	0.09	1.2	0.4	0.08
<b>Spare Parts</b>	1,500,000	2	3,000,000						



# Conclusions

---

---

- **Need help from outside collaborators on design and fabrication of the 2<sup>nd</sup> harmonic system.**
- **Beam loading compensation techniques same as present system utilizing a combination of direct rf feedback, digital comb filter, and feed forward.**
- **Cavity will require much of the R&D effort to solve tuner and cavity cooling issues, reliable operation at 100KV gradient, and HOM dampers.**
- **If ICD-2 is the route, R&D efforts should start soon there after so prototype cavities (fundamental & 2<sup>nd</sup> harmonic) can be designed, fabricated, and tested in the present MI enclosure with beam .**